


Slings

A collection of various lifting equipment is displayed on a grey, diamond-plate metal surface. The items include: a yellow webbing sling with a red hook; a green webbing sling with a green hook; a purple webbing sling with a metal shackle; a green webbing sling with an orange label; a yellow webbing sling with a red label; a red webbing sling with a red hook; a black webbing sling with a red hook; a brown webbing sling with a brown hook; a metal chain with a green hook; a metal chain with a brown hook; a metal chain with a metal shackle; and a metal chain with a metal shackle. The equipment is arranged in a way that shows different types and colors of slings and chains.



BLP-100

Single leg sling with
standard eyes each end



BLP-101

Single leg sling with
standard eye one end and
thimble eye other end



BLP-102

Single leg sling with thimble
eye each end

Features:

- Flemished eye splice, not a Texas tucked or turn back eye splice
- Heavy gauge stainless steel tag in accordance with ASME B30.9 and API RP2D
- Quality controlled swaging process with paint verification
- 6x19 class IWRC EIP bright wire rope supplied standard on 1/4" – 1-1/8"
- 6x37 class IWRC EIP bright wire rope supplied standard on 1-1/4" and larger
- Proof testing available upon request
- Design factor 5 to 1

How to order:

- Specify part number and length in feet when ordering




WARNING

See wire rope sling warnings page
for warnings and inspection criteria

Dia. of Rope In.	Part Numbers			Min. Length ft'-in"	Standard Eye Dimensions		Rated Capacities in Short Tons		
	BLP-100	BLP-101	BLP-102		W"	L"	Choker	Vertical	Vertical Basket
1/4"	11010103	11010603	11060603	1-6	2	4	.48	.65	1.3
3/8"	11010105	11010605	11060605	2	3	6	1.1	1.4	2.8
1/2"	11010107	11010607	11060607	2-6	4	8	1.9	2.5	5.1
5/8"	11010109	11010609	11060609	3	5	10	2.9	3.9	7.8
3/4"	11010110	11010610	11060610	3-6	6	12	4.1	5.6	11.2
7/8"	11010111	11010611	11060611	4	7	14	5.6	7.6	15.2
1"	11010112	11010612	11060612	4-6	8	16	7.2	9.8	19.6
1-1/8"	11010113	11010613	11060613	5	9	18	9.1	12	24
1-1/4"	11010114	11010614	11060614	5-6	10	20	11	15	30
1-3/8"	11010115	11010615	11060615	6	11	22	13	18	36
1-1/2"	11010116	11010616	11060616	7	12	24	16	21	42
1-3/4"	11010118	11010618	11060618	8	14	28	21	28	56
2"	11010120	11010620	11060620	9	16	32	28	37	74
2-1/4"	11010122	11010622	11060622	10	18	36	35	44	88
2-1/2"	11010124	11010624	11060624	11-6	20	40	42	54	108
2-3/4"	11010125			12	22	44	51	65	130
3"	11010127			13	24	48	60	77	154
3-1/2"	11010131			16-6	32	64	79	102	204
3-3/4"	11010132			18	36	72	90	115	230
4"	11010133			20	40	80	101	130	260
4-1/2"	11010134			24	50	100	124	160	320

Note:

- Specify wire rope construction, grade, and finish if other than standard



BLP-103

Single leg sling with alloy master link and thimble on top and thimble eye on bottom



BLP-104

Single leg sling with alloy master link and thimble on top and thimble eye & eye hook on bottom



BLP-105

Single leg sling with alloy master link and thimble on top and thimble eye & auto-locking hook on bottom

Features:

- Flemished eye splice, not a Texas tucked or turn back eye splice
- Heavy gauge stainless steel tag in accordance with ASME B30.9 and API RP2D
- Quality controlled swaging process with paint verification
- 6x19 class IWRC EIP bright wire rope supplied standard on 1/4" – 1-1/8"
- 6x37 class IWRC EIP Bright wire rope supplied standard on 1-1/4" and larger
- Proof testing available upon request
- Design factor 5 to 1

How to order:

- Specify part number and length in feet when ordering


WARNING

See wire rope sling warnings page for warnings and inspection criteria

Dia of Rope In."	Part Numbers			Min. Length ft'-in"	Standard Eye Dimensions		Rated Capacities in Short Tons		
	BLP-103	BLP-104	BLP-105		W"	L"	Choker	Vertical	Vertical Basket
1/4"	11210603	11212903	11213103	1-6	2	4	.48	.65	1.3
3/8"	11210605	11212905	11213105	2	3	6	1.1	1.4	2.8
1/2"	11210607	11212907	11213107	2-6	4	8	1.9	2.5	5.1
5/8"	11210609	11212909	11213109	3	5	10	2.9	3.9	7.8
3/4"	11210610	11212910	11213110	3-6	6	12	4.1	5.6	11.2
7/8"	11210611	11212911	11213111	4	7	14	5.6	7.6	15.2
1"	11210612	11212912	11213112	4-6	8	16	7.2	9.8	19.6
1-1/8"	11210613	11212913	11213113	5	9	18	9.1	12	24
1-1/4"	11210614	11212914	11213114	5-6	10	20	11	15	30
1-3/8"	11210615	11212915	11213115	6	11	22	13	18	36
1-1/2"	11210616	11212916	11213116	7	12	24	16	21	42
1-3/4"	11210618	11212918	11213118	8	14	28	21	28	56
2"	11210620	11212920		9	16	32	28	37	74
2-1/4"	11210622	11212922		10	18	36	35	44	88
2-1/2"	11210624	11212924		11-6	20	40	42	54	108
2-3/4"	11210625			12	22	44	51	65	130
3"	11210627			13	24	48	60	77	154
3-1/2"	11210631			16-6	32	64	79	102	204
3-3/4"	11210632			18	36	72	90	115	230
4"	11210633			20	40	80	101	130	260
4-1/2"	11210634			24	50	100	124	160	320

Note:

- Hook supplied standard without latch. Specify if hook requires latch
- Specify wire rope construction, grade, and finish if other than standard



BLP-180

8-Part braided sling with slip-thru thimble on top, with sliding choker hook and casing thimble on bottom



BLP-181

Single leg, 8-part braided sling with slip-thru thimble on top and casing thimble on bottom

Features:

- Extremely flexible and durable
- Heavy gauge stainless steel tag in accordance with ASME B30.9 and API RP2D
- Repairable if hardware passes inspection and proof testing
- 7x19 galvanized cable standard on 1/8" through 3/8"
- 6x37 class EIP IWRC bright standard on 7/16" and above
- Proof testing available upon request
- Design factor 5 to 1



Optional sliding choker hook with latch available in 1/8", 3/16", and 1/4" upon request

How to order:

- Specify part number and length in feet when ordering


WARNING

See wire rope sling warnings page for warnings and inspection criteria

8-parts Wire Rope Components Dia.	Part Number		Approx. Body Diameter	Rated Capacities in Short Tons		
	BLP-180	BLP-181		Vertical	Choker	Vertical Basket
1/8"	18075201	18070801	5/8"	1.1	1.0	2.2
3/16"	18075202	18070802	3/4"	2.4	2.1	4.7
1/4"	18075203	18070803	1-1/8"	3.9	3.4	7.8
5/16"	18075204	18070804	1-3/8"	5.5	4.8	11.0
3/8"	18075205	18070805	1-3/4"	8.1	7.1	16.1
7/16"	18075206	18070806	2"	11.4	10.0	22.8
1/2"	18075207	18070807	2-1/4"	14.9	13.0	29.8

Note:

- Specify wire rope construction, grade, and finish if other than standard



BLP-200

Two leg bridle sling with alloy master link and thimbles on top, with thimbles and eye hooks on bottom



BLP-201

Two leg bridle sling with alloy master link and thimbles on top, with thimbles only on bottom

Features:

- Flemished eye splice, not a Texas tucked or turn back eye splice
- Heavy gauge stainless steel tag in accordance with ASME B30.9 and API RP2D
- Quality controlled swaging process with paint verification
- 6x19 class IWRC EIP bright wire rope supplied standard on 1/4" – 1-1/8"
- 6x37 class IWRC EIP bright wire rope supplied standard on 1-1/4" and larger
- Proof testing available upon request
- Design factor 5 to 1

How to order:

- Specify part number and length in feet when ordering


WARNING

See wire rope sling warnings page for warnings and inspection criteria

Wire Rope Dia.	Part Number		Min. Length Ft - In	Capacities in Short Tons			Standard Hardware	
	BLP-200	BLP-201		Capacities from the Horizontal				
				60°	45°	30°	Alloy Master Link	Eye Hooks
1/4"	21212903	21210603	1-3	1.1	.92	.65	1/2"	3/4 ton -S-320N-C
3/8"	21212905	21210605	1-8	2.5	2.0	1.4	3/4"	1.5 ton S-320N-C
1/2"	21212907	21210607	2-0	4.4	3.6	2.5	1"	3 ton S-320N-C
5/8"	21212909	21210609	2-4	6.8	5.5	3.9	1-1/4"	5 ton S-320N-C
3/4"	21212910	21210610	2-9	9.7	7.9	5.6	1-1/4"	7 ton S-320N-A
7/8"	21212911	21210611	3-3	13	11	7.6	1-1/4"	7.5 ton S-320N-C
1"	21212912	21210612	3-6	17	14	9.8	1-1/2"	10 ton S-320N-C
1-1/8"	21212913	21210613	4-0	21	17	12	1-3/4"	15 ton S-320N-A
1-1/4"	21212914	21210614	4-6	26	21	15	1-3/4"	15 ton S-320N-A
1-3/8"	21212915	21210615	5-0	31	25	18	2"	20 ton S-320-C
1-1/2"	21212916	21210616	5-6	37	30	21	2"	22 ton S-320N-A
1-3/4"	21212918	21210618	6-6	49	40	28	2-1/2"	30 ton S-320-A
2"	21212920	21210620	8-0	63	52	37	2-3/4"	37 ton S-320-A

Note:

- Hooks supplied standard without latches. Specify if hooks require latches
- Specify wire rope construction, grade, and finish if other than standard
- Specify master link and hooks size if other than standard



BLP-300

Three leg bridle with alloy master link and thimbles on top, with thimbles and eye hooks on bottom



BLP-301

Three leg bridle with alloy master link and thimbles on top, with thimbles only on bottom

Features:

- Flemished eye splice, not a Texas tucked or turn back eye splice
- Heavy gauge stainless steel tag in accordance with ASME B30.9 and API RP2D
- Quality controlled swaging process with paint verification
- 6x19 class IWRC EIP bright wire rope supplied standard on 1/4" – 1-1/8"
- 6x37 class IWRC EIP bright wire rope supplied standard on 1-1/4" and larger
- Proof testing available upon request
- Design factor 5 to 1

How to order:

- Specify part number and length in feet when ordering


WARNING

See wire rope sling warnings page for warnings and inspection criteria

Wire Rope Dia.	Part Numbers		Min. Length Ft - In	Capacities in Short Tons			Standard Hardware	
	BLP-300	BLP-301		Capacities from the Horizontal				
				60°	45°	30°	Alloy Master Link	Eye Hooks
1/4"	31212903	31210603	1-3	1.7	1.4	.97	5/8"	3/4 ton -S-320N-C
3/8"	31212905	31210605	1-8	3.7	3.0	2.2	7/8"	1.5 ton S-320N-C
1/2"	31212907	31210607	2-0	6.6	5.4	3.8	1-1/4"	3 ton S-320N-C
5/8"	31212909	31210609	2-4	10	8.3	5.9	1-1/4"	5 ton S-320N-C
3/4"	31212910	31210610	2-9	15	12	8.4	1-1/2"	7 ton S-320N-A
7/8"	31212911	31210611	3-3	20	16	11	1-1/2"	7.5 ton S-320N-C
1"	31212912	31210612	3-6	26	21	15	1-3/4"	10 ton S-320N-C
1-1/8"	31212913	31210613	4-0	31	26	18	2"	15 ton S-320N-A
1-1/4"	31212914	31210614	4-6	38	31	22	2"	15 ton S-320N-A
1-3/8"	31212915	31210615	5-0	46	38	27	2-1/4"	20 ton S-320-C
1-1/2"	31212916	31210616	5-6	55	45	32	2-1/2"	22 ton S-320N-A
1-3/4"	31212918	31210618	6-6	74	60	42	-	30 ton S-320-A
2"	31212920	31210620	8-0	95	78	55	-	37 ton S-320-A

Note:

- Hooks supplied standard without latches. Specify if hooks require latches
- Specify master link size if specific dimensions are required
- Specify wire rope construction, grade, and finish if other than standard
- Specify master link and hook size if other than standard
- Rated capacity based on all three legs carrying the load equally



BLP-400

Four leg bridle slings with alloy master link and thimbles on top, with thimbles and eye hooks on bottom



BLP-401

Four leg bridle slings with alloy master link and thimbles on top, with thimbles only on bottom

Features:

- Flemished eye splice, not a Texas tucked or turn back eye splice
- Heavy gauge stainless steel tag in accordance with ASME B30.9 and API RP2D
- Quality controlled swaging process with paint verification
- 6x19 class IWRC EIP bright wire rope supplied standard on 1/4" – 1-1/8"
- 6x37 class IWRC EIP bright wire rope supplied standard on 1-1/4" and larger
- Proof testing available upon request
- Design factor 5 to 1

How to order:

- Specify part number and length in feet when ordering



WARNING

See wire rope sling warnings page for warnings and inspection criteria

Wire Rope Dia.	Part Number		Min. Length Ft - In	Capacities in Short Tons			Standard Hardware	
	BLP-400	BLP-401		Capacities from the Horizontal				
				60°	45°	30°	Alloy Master Link	Eye Hooks
1/4"	41212903	41210603	1-3	2.2	1.8	1.3	3/4"	3/4 ton -S-320N-C
3/8"	41212905	41210605	1-8	5.0	4.1	2.9	1"	1.5 ton S-320N-C
1/2"	41212907	41210607	2-0	8.8	7.1	5.1	1-1/4"	3 ton S-320N-C
5/8"	41212909	41210609	2-4	14	11	7.8	1-1/4"	5 ton S-320N-C
3/4"	41212910	41210610	2-9	19	16	11	1-1/2"	7 ton S-320N-A
7/8"	41212911	41210611	3-3	26	21	15	1-3/4"	7.5 ton S-320N-C
1"	41212912	41210612	3-6	34	28	20	2"	10 ton S-320N-C
1-1/8"	41212913	41210613	4-0	42	34	24	2-1/4"	15 ton S-320N-A
1-1/4"	41212914	41210614	4-6	51	42	30	2" **	15 ton S-320N-A
1-3/8"	41212915	41210615	5-0	62	50	36	2-1/2" **	20 ton S-320-C
1-1/2"	41212916	41210616	5-6	73	60	42	2-3/4" **	22 ton S-320N-A
1-3/4"	41212918	41210618	6-6	98	80	57	2-3/4" **	30 ton S-320-A
2"	41212920	41210620	8-0	127	104	73	4" **	37 ton S-320-A

Note:

- ** Alloy, sub-assembly used
- Hooks supplied standard without latches. Specify if hooks require latches
- Specify master link size if specific dimensions are required
- Specify wire rope construction, grade, and finish if other than standard
- Specify master link and hook size if other than standard
- Notify BLP at time of purchase if used on a personnel lifting basket
- Rated capacity based on all four legs carrying the load equally



BLP-203

Two leg bridle with alloy master link and thimbles on top, with thimbles and sorting hooks on bottom



BLP-303

Three leg bridle with alloy master link and thimbles on top, with thimbles and sorting hooks on bottom



BLP-403

Four leg bridle with alloy master link and thimbles on top, with thimbles and sorting hooks on bottom

Features:

- Flemished eye splice, not a Texas tucked or turn back eye splice
- Heavy gauge stainless steel tag in accordance with ASME B30.9 and API RP2D
- Quality controlled swaging process with paint verification
- 6x19 class IWRC EIP bright wire rope supplied standard
- Proof testing available upon request
- Design factor 5 to 1

How to order:

- Specify part number and length in feet when ordering




See wire rope sling warnings page for warnings and inspection criteria

Wire Rope Dia.	Part Number			Min. Length Ft - In	Capacities in Short Tons			Standard Hardware
	BLP-203	BLP-303	BLP-403		Capacities from the Horizontal			
					BLP-203	BLP-303	BLP-403	Sorting Hooks
					60°	60°	60°	2 ton A-378
1/2"	21213307	31213307	41213307	2-0	3.4	5.1	6.9	2 ton A-378
5/8"	21213309	31213309	41213309	2-4	3.4	5.1	6.9	2 ton A-378

Note:

- Specify wire rope construction, grade, and finish if other than standard
- Rated capacity based on all legs carrying the load equally



BLP-500

Single leg socket line with open swage socket each end, pins parallel



BLP-501

Single leg socket line with open swage socket each end, pins at right angles



BLP-502

Single leg socket line with open swage socket one end and closed swage socket other end, pins parallel



BLP-503

Single leg socket line with open swage socket one end and closed swage socket other end, pins at right angles



BLP-504

Socket line with closed swage socket each end, pins parallel



BLP-505

Socket line with closed swage socket each end, pins at right angles

Features:

- Heavy gauge stainless steel tag in accordance with ASME B30.9 and API RP2D
- Proof tested to 2X Rated Capacity
- 6x19 class IWRC EIP bright wire rope supplied standard
- 100% termination efficiency
- Design factor 5 to 1

WARNING

See wire rope sling warnings page for warnings and inspection criteria


How to order:

- Specify part number and length in feet when ordering

Dia. of Rope	BLP-500	BLP-501	BLP-502	BLP-503	BLP-504	BLP-505	Min. Sling Length ft.-in.	EIPS Rated Capacity in Short Tons	EEIP Rated Capacity in Short Tons
3/8"	11151505	11202005	11151405	11201905	11141405	11191905	1-0	1.5	1.7
1/2"	11151507	11202007	11151407	11201907	11141407	11191907	1-8	2.7	2.9
5/8"	11151509	11202009	11151409	11201909	11141409	11191909	2-0	4.1	4.5
3/4"	11151510	11202010	11151410	11201910	11141410	11191910	2-5	5.9	6.5
7/8"	11151511	11202011	11151411	11201911	11141411	11191911	2-10	8.0	8.8
1"	11151512	11202012	11151412	11201912	11141412	11191912	3-2	10	11.4
1-1/8"	11151513	11202013	11151413	11201913	11141413	11191913	3-7	13	14.3
1-1/4"	11151514	11202014	11151414	11201914	11141414	11191914	4-0	16	17.6
1-3/8"	11151515	11202015	11151415	11201915	11141415	11191915	4-5	19	20.2
1-1/2"	11151516	11202016	11151416	11201916	11141416	11191916	4-9	23	25
1-3/4"	11151518	11202018	11151418	11201918	11141418	11191918	5-5	31	33.8
2"	11151520	11202020	11151420	11201920	11141420	11191920	6-4	40	43.4

Note:

- Specify wire rope construction, grade, and finish if other than standard



BLP-600

Socket line with open spelter socket
each end, pins parallel



BLP-601

Socket line with open spelter socket each
end, pins at right angles



BLP-602

Socket line with open spelter socket one end and
closed spelter socket other end, pins parallel



BLP-603

Socket line with open spelter socket one end and
closed spelter socket other end, pins at right angles



BLP-604

Socket line with closed spelter
socket each end, pins parallel



BLP-605

Socket line with closed spelter socket
each end, pins at right angles



BLP-606

Socket line with mooring spelter socket
each end, bails parallel



BLP-607

Socket line with mooring spelter socket
each end, bails at right angles

Features:

- Heavy gauge stainless steel tag in accordance with ASME B30.9 and API RP2D
- Proof tested to 2X Rated Capacity
- Spelter sockets attached with WIRELOCK®
- 6x19 Class IWRC EIP bright wire rope supplied standard up to 2"
- 6x36 Class IWRC EIP bright wire rope supplied standard on 2-1/2" and larger
- 100% termination efficiency
- Design factor 5 to 1

How to order:

- Specify part number and length in feet when ordering


WARNING

See wire rope sling warnings page
for warnings and inspection criteria

Dia. of Rope	BLP-600	BLP-601	BLP-602	BLP-603	BLP-604	BLP-605	BLP-606	BLP-607	Min. Sling Length ft.-in.	EIPS Rated Capacity in Short Tons	EEIP Rated Capacity in Short Tons
3/8"	11131305	11181805	11131205	11181705	11121205	11171705	-	-	1-0	1.5	1.7
1/2"	11131307	11181807	11131207	11181707	11121207	11171707	-	-	1-3	2.7	2.9
5/8"	11131309	11181809	11131209	11181709	11121209	11171709	-	-	1-6	4.1	4.5
3/4"	11131310	11181810	11131210	11181710	11121210	11171710	-	-	1-9	5.9	6.5
7/8"	11131311	11181811	11131211	11181711	11121211	11171711	-	-	2-0	8.0	8.8
1"	11131312	11181812	11131212	11181712	11121212	11171712	-	-	2-6	10	11.4
1-1/8"	11131313	11181813	11131213	11181713	11121213	11171713	-	-	2-9	13	14.3
1-1/4"	11131314	11181814	11131214	11181714	11121214	11171714	-	-	3-0	16	17.6
1-3/8"	11131315	11181815	11131215	11181715	11121215	11171715	-	-	3-0	19	20.2
1-1/2"	11131316	11181816	11131216	11181716	11121216	11171716	-	-	3-3	23	25
1-3/4"	11131318	11181818	11131218	11181718	11121218	11171718	-	-	4-3	31	33.8
2"	11131320	11181820	11131220	11181720	11121220	11171720	11111120	11161620	4-9	40	43.4
2-1/4"	11131322	11181822	11131222	11181722	11121222	11171722	11111122	11161622	5-0	49.4	56.4
2-1/2"	11131324	11181824	11131224	11181724	11121224	11171724	11111124	11161624	5-9	60	66
2-3/4"	11131325	11181825	11131225	11181725	11121225	11171725	11111125	11161625	6-2	72	79
3"	11131327	11181827	11131227	11181727	11121227	11171727	11111127	11161627	6-6	85	94
3-1/2"	11131331	11181831	11131231	11181731	11121231	11171731	11111131	11161631	7-6	113	124

Note:

- Specify wire rope construction, grade, and finish if other than standard



BLP-608

Single leg sling with hawser
thimbles each end

Features:

- Flemished eye splice, not a tucked or returned eye splice
- Heavy gauge stainless steel tag in accordance with ASME B30.9 and API RP2D
- Quality controlled swaging process with paint verification
- 6x19 Class IWRC EIP bright wire rope supplied standard up to 2"
- 6x36 Class IWRC EIP bright wire rope supplied standard on 2-1/2" and larger
- Hot galvanized cast alloy steel Hawser thimble each end
- Proof testing available on request
- Design factor 5 to 1

How to order:

- Specify part number and length in feet when ordering

WARNING

See wire rope sling warnings page
for warnings and inspection criteria


Dia. of Rope	Part Number	Min. Sling Length ft.-in.	Rated Capacity Vertical (short tons)
5/8"	11101009	3	3.9
3/4"	11101010	3-6	5.6
7/8"	11101011	4	7.6
1"	11101012	4-6	9.8
1-1/8"	11101013	5	12
1-1/4"	11101014	5-6	15
1-3/8"	11101015	6	18
1-1/2"	11101016	7	21
1-3/4"	11101018	8	28
2"	11101020	9	37
2-1/4"	11101022	10	44
2-1/2"	11101024	11	54
2-3/4"	11101025	12	65
3"	11101027	13	77

Note:


- Specify wire rope type, finish, and construction if other than standard



TC
Tea cup carrier for handling box
culverts



BLP-106
Single leg sling with standard eye
top end and standard swage button
bottom end



BLP-207
Two leg bridle with alloy master link
and thimbles top end and standard
swage buttons bottom end

Features:

- Flemished eye splice, not a Texas tucked or turn back eye splice
- Heavy gauge stainless steel tag in accordance with ASME B30.9 and API RP2D
- Quality controlled swaging process with paint verification
- 6x19 class IWRC EIP bright wire rope supplied standard
- Proof testing available upon request
- Design factor 5 to 1

How to order:

- Specify part number and length in feet when ordering

WARNING

See wire rope sling warnings page
for warnings and inspection criteria

Dia of Rope	Part Numbers			Min. Sling Length	Loop Dim. Inches		Rated Capacities in Short Tons		After Swage Dimensions (in.)
	Tea Cup	BLP-106	BLP-207		L	W	Single Leg 90°	Two Legs 60°	Maximum After Swage Dimension
5/8"	TC-1	11013909	21213909	3'	5	10	3.9	6.7	1.42
3/4"	TC-2	11013910	21213910	3'-6"	6	12	5.6	9.6	1.55
7/8"	TC-2	11013911	21213911	4'	7	14	7.6	13.1	1.80
1"	TC-3	11013912	21213912	4'-6"	8	16	9.8	16.97	2.05
1-1/8"	TC-3	11013913	21213913	5'	9	18	12	20.7	2.30
1-1/4"	TC-4	11013914	21213914	5'-6"	10	20	15	25.9	2.56
1-3/8"	TC-5	11013915	21213915	6'	11	22	18	31.1	2.81
1-1/2"	TC-5	11013916	21213916	7'	12	24	21	36.3	2.81

Note:

- Specify wire rope construction, grade, and finish if other than standard

⚠ WIRE ROPE SLING WARNINGS

When you inspect a wire rope sling, it shall be taken out of service immediately and returned for repair or replacement when any of the below defects are present.

Missing or illegible sling identification (tag)		Kinking, crushing, bird-caging, or any other damage to the rope structure	
For single part slings, 10 randomly distributed broken wires in one lay length or 5 broken wires in one strand in one rope lay		Evidence of heat damage	
For cable-laid slings, 20 broken wires per braid		End attachments that are cracked, deformed, or worn	
For 6-part braided slings, 20 broken wires per braid		Severe corrosion of the rope, end attachments, or fittings	
For 8-part braided slings, 40 broken wires per braid		Damaged hooks per ASME B30.10	
Severe localized abrasion or scraping		Damaged rigging hardware per ASME B30.26	

and... Any condition that causes doubt about the continued use of the sling